CADANGAN MEMBINA PASAR SEMENTARA (TRANSIT) UNTUK PASAR WAMMES, DALAWSKI OT SERKAWAL KEMBANGAN, SELANGOR DARUL EHSAN

ITEM	DESCRIPTION	UNIT	QTY	RATE (RM)	AMOUNT (RM)
	Notes: Rates for the following items shall include any temporary access, dewatering, sand bags, removal of damaged structures, rubbish, etc and reinstatement of all damaged drains, roads, earthworks, turfing, etc.				
	Contractor must submit their method statement, list of plant and equipment to be used, etc. for drainage works to Consultant prior to commencement of works, for their approval.				
	Contractor must ensure that the plant used for the works is not too heavy as to damage the existing road and paved walkways				
	Contractor shall maintain and make sure that all waterways/water courses must be free of silt at all time and must take measure such as putting in temporary earth drains, silt traps, etc. to prevent silt from flowing back into the pond whilst desilting works is being carried out				
	BILL. NO. 2 : EARTHWORKS (ALL PROVISIONAL)				
	SITE CLEARING				
А	Demolition of existing Concrete slab and other related concrete stucture. Any remaining structure shall be dispose off the site and make good of any existing services.	ITEM	-	-	
В	Deposit suitable earth filling thoroughly compact in consolidated layer, spread, and level as approved by the S.O. to the site	M3	1,200		
С	Excavation in bulk or in the open/trim existing platform, material other than topsoil or unsuitable material to the level and profiles in cut areas within the site including other related works	М3	1,090		
TOTAL CARRIED TO SUMMARY OF TENDER (RM)					