Dokumen Meja Terkawal kerja-kerja ujian makmal bagi projek penyelenggaraan jalan di kawasan bp 6 & BP 7, MAJLIS BANDARAYA SUBANG JAYA, SELANGOR DARUL EHSAN.

BIL	HURAIAN KERJA	UNIT	KADAR (RM)
	TESTING OF ALL MATERIAL WORKS :		
	Testing of all material and works for <b>AC/SMA</b> to ensure compliance of the Specification and Contract :-		
А	Preparation, determination, and analysis for labrotary specimen for an <b>Extraction of bitumen from binding mixture</b> in accordance with ASTM D 1559/ASTM D 2726 by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O. and his representative	NOS	110.00
В	Preparation, determination, and analysis for labrotary specimen for <b>Seive analysis of extracted aggregate</b> in accordance with ASTM C 131/AASHTO Test Method T 104 by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O and his representative	NOS	60.00
С	Preparation, determination, and analysis for labrotary specimen for <b>Marshal test</b> including stability test, flow test, stiffness test, air void in mix (VIM) voids in aggregate filled with bitumen (VFB) in accordance with ASTM D 1559 by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O. and his representative	SET	300.00
D	Preparation, determination, and analysis for labrotary specimen for <b>Density of Core</b> by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O. and his representative	NOS	30.00
Е	Preparation, determination, and analysis for labrotary specimen for <b>Binder drain-down test</b> in accordance with AASHTO Standards T245 by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O and his representative	NOS	70.00

## Dokumen Meja Terkawal

BIL	HURAIAN KERJA	UNIT	KADAR (RM)
	TESTING OF ALL MATERIAL WORKS (cont'd) :		
	Testing of all material and works for <b>AC</b> / <b>SMA</b> to ensure compliance of the Specification and Contract :-		
A	Preparation, determination, and analysis for labrotary specimen for <b>Tray Test</b> refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O. and his representative	NOS	20.00
В	Preparation, determination, and analysis for labrotary specimen for <b>Coring Works</b> by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O. and his representative	NOS	90.00
С	Preparation, determination, and analysis for labrotary specimen for <b>Surface Irregularities Testing (rolling straight edge)</b> by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of S.O. and his representative	LANE/M	1.00
D	Preparation, determination, and analysis for labrotary specimen for <b>Tranverse Irragularities Testing (3m straight edge)</b> by refered to JKR/SPJ/2008-S4 Specification including report of the test result to be submitted to MBSJ according the instruction of		
	S.O. and his representative	NOS	13.00

	an di dalam Jadual Kadar Harga pihak saya/kami telah
bersetuju dengan kadar tawaran diskaun sebany	/ak *%(dengan perkataan :
	_) kepada pihak Majlis Bandaraya Subang Jaya
(dibawa ke Borang Sebut Harga).	
(Tandatangan Kontraktor)	(Tandatangan Saksi)
Nama :	Nama :
No. KP:	No. KP :
Atas Sifat :	Alamat :

<sup>\*</sup> sila potong mana yang tidak berkenaan

<sup>\*\*</sup> sila isikan peratus yang ditawarkan kepada dua titik perpuluhan. (e.g 20.20)