

BIL	HURAIAN KERJA	UNIT	KUANTITI	KADAR	JUMLAH (RM)
	MEMBEKAL DAN MEMASANG				
	PEMASANGAN SALURAN UDARA DUCTING SUPPLY AND RETURN				
A	To renovate, Supply And Return air ductwork Galvanised Steel Sheet Metal Duct Works for ROOFTOP UNIT NO.1 (capacity 32.0 H.P.) (Cooling capacity 320,000 Btu/h, 10,000cfm, 94kW) (Existing Duct Supply = 1500mm x 1200mm) (Existing Duct Return = 1200mm x 300mm) with hi-external static c/w fire damper, guide vanes, splitter c/w fittings, heavy duty glue connection, double layer ducting for exposed duct, External and Internal Insulation PE Foam 25mm, open cell internal insulation 25mm, hangers, and other necessary accessories dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.	M2	48		
B	To renovate, Supply And Return air ductwork Galvanised Steel Sheet Metal Duct Works for ROOFTOP UNIT NO. 2 (capacity 32.0 H.P.) (Cooling capacity 320,000 Btu/h, 10,000cfm, 94kW) (Existing Duct Supply = 1500mm x 1200mm) (Existing Duct Return = 1200mm x 300mm) with hi-external static c/w fire damper, guide vanes, splitter c/w fittings, heavy duty glue connection, double layer ducting for exposed duct, External and Internal Insulation PE Foam 25mm, open cell internal insulation 25mm, hangers, and other necessary accessories dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.	M2	48		
C	To renovate, Supply And Return air ductwork Galvanised Steel Sheet Metal Duct Works for ROOFTOP UNIT NO.3 (Capacity 12.0 H.P.) (Cooling capacity 112,000 Btu/h, 3,500cfm, 33kW) (Existing Duct Supply = 900mm x 300mm) (Existing Duct Return = 1300mm x 500mm) with hi-external static c/w fire damper, guide vanes, splitter c/w fittings, heavy duty glue connection, double layer ducting for exposed duct, External and Internal Insulation PE Foam 25mm, open cell internal insulation 25mm, hangers, and other necessary accessories dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.	M2	18		
D	Supply and install Jet Diffuser + OBD Fan Blade 12inch c/w Flexible Ducting Fibreglass 12 inch hole diameter, fitting collar, heavy duty glue connection, steel wire hangers and other necessary termasuk kerja menanggalkan diffuser lama dan kemasan semula dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil	Nos	30		
E	Supply and install Louver Return Air Grille (900mm x 1000mm) c/w fitting collar, heavy duty glue connection, steel wire hangers and other necessary dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.	Nos	3		
F	Kerja-kerja membaiki, menampal menggunakan gam heavy duty, membersihkan saluran udara ducting dan dinding plywood sedia ada dan lain kerja-kerja berkaitan mengikut arahan P.P atau wakil P.P.	Lot	1		
JUMLAH DIBAWA KE HADAPAN (RM) :					

KERJA-KERJA MENAIKTARAF SISTEM PENGHAWA DINGIN JENIS AIR COOLED DUCTED LENGKAP DENGAN BUILDING AUTOMATION SYSTEM SERTA KERJA-KERJA ELEKTRIK BERKAITAN DI DEWAN SERBAGUNA SS15 SUBANG JAYA BAGI MAJLIS BANDARAYA SUBANG JAYA

Dokumen Meja Terkawal

BIL	HURAIAN KERJA	UNIT	KUANTITI	KADAR	JUMLAH (RM)
	JUMLAH DIBAWA DARI BELAKANG (RM) :				
	PEMASANGAN SALURAN UDARA <i>DUCTING SUPPLY AND RETURN (samb.)</i>				
	Kerja-Kerja Platform <i>Structure AHU</i>				
A	<i>Design, supply and install Platform steel structures including cutting, forming, welding, heavyduty screw wallplug and ensuring joist & grates Non-Corroton Galvanised Coating including all necessary supports as specified for MS C-Channel 100mm x 50mm x 6mm dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.</i>	M	88		
B	<i>Design, supply and install Platform steel structures including cutting, forming, welding, heavyduty screw wallplug and ensuring joist & grates Non-Corroton Galvanised Coating including all necessary supports as specified for Platform Grates Expanded Metal Diamond Mesh (SWD 22mm x LWD 57mm x thickness 2.5mm) dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.</i>	M2	40		
C	<i>Design, supply and install Vertical Fixed Galvanised steel Ladders including cutting, forming, welding and Non-Corroton Galvanised Coating including all necessary supports as specified (Weight Capacity 180KG, Distance between Rung 10 inch, Inside Width Ladder 16 inch, Overall Lenght 3600mm) dan lain-lain kerja yang berkaitan mengikut arahan P.P atau wakil P.P.</i>	Lot	2		
JUMLAH DIBAWA KE BORANG RINGKASAN SEBUT HARGA (RM) :					